


2. Roof Plan 1:150



S-01 Building Section 1:75

**ROOF NOTES**  
Resincoat G28 G.C.i roofing sheets and ridge cap on 100mmx50mm trussed rafters and struts. 75mmx50mm purlins, 100mmx50mm ceilingjoists, trusses at 600mm c/c, 100mm x50mm wall plate, 200mmx25mm painted fasciaboard to s.e's details. T & G ceiling on 50mmx 50mm brander at 600 c/c, 600mmeaves overhang to details, roof pitches at 30 degrees.


**RING BEAM**  
150mmx350mm ring beam concrete mix 1:2:3 with 4Y12 main bars with Y8 stirrups @300mm spacing

100mmx75mm wall plate on 150mmx350mm ring beam concrete mix 1:2:3 with Y12 main bars with Y8 stirrups @300mm spacing


150mm thick RC wall concrete mix 1:2:3 to s.e's details

150mm thick ground floor slab concrete mix 1:2:3 on 1000 gauge DPM on 50mmthick well rammed anti termite treated murram blinding layer on a well compacted 300mm thick hardcore filling


600mmx200mm thick foundation strip concrete mix 1:2:3 foundation depth to be determined on site.



West Elevation 1:100



East Elevation 1:100




North Elevation 1:100



South Elevation 1:100

FINISHES SCHEDULE



- 1:3 mix cement sand floor screed not less than 20mm level or to fall as necessary.
- 50mm thick 600x600mm precast concrete paving slabs laid on and including 50mm sand bed and pointed in cement and sand.
- 3 coats of approved plastic emulsion paint to 13mm 1:2:3 cement sand lime mix plastered surfaces of internal wall/ceiling surface.
5. fair face finish to machine cut external walls with cement sand (1:3) mix mortar pointing forming half round recessed joints.

NOTES

1. All dimensions in mm unless stated otherwise.
2. Only figured dimensions to be used.
3. All dimensions to be checked on site and any discrepancy referred to the Architect.
4. All foundations to be carried to hard ground bottom to structural engineer's details and specifications.
5. All reinforced concrete works to structural engineer's details and specifications.
6. All drain pipes passing under the slab to be encased in 150mm thick concrete.
- 7.Pv denotes permanent ventilations above doors and window openings where shown except toilets and bathrooms doors.
8. D.P.C denotes damp proof course to be provided on all walls at least 150mm above ground level.
9. All soil vent pipes to be provided with dome on top.
10. Water meter to be 300mm above ground level.
11. 75mm diameter rain water down pipes to be provided with rain water trough off shoe away from the wall.
12. All drains and plumbing works to be constructed according to by-laws.
13. All walls less than 200mm thick to be reinforced with hoop iron at every alternative courses.

REVISIONS

REF	AMENDMENTS	PARTICULARS	DATE	INITIAL

REFERENCE DRAWINGS


Drawn by: Nyongesa S.K. Date: FEBRUARY 2018  
Checked by: E.P.N.G.W & W.  
Architect

**CM NYONGESA S.K**  
**BACHELOR OF THE BUILT ENVIRONMENT (CONSTRUCTION MANAGEMENT) YEAR FOUR**  
**PROJECT B 2017/2018**  
**REG:EABQ/01775/2014**


Client: THE TECHNICAL UNIVERSITY OF KENYA  
HAILLE SELLASIE AVENUE  
NAIROBI  
Signature: \_\_\_\_\_  
P.O. BOX: 52428 - 00200 - NAIROBI - KENYA  
TEL: \_\_\_\_\_  
E-mail: \_\_\_\_\_

Location: **11381/19 NAIROBI COUNTY**


Jurisdiction: **BCM DEGREE FULFILMENT**  
Job Title: **PROPOSED CHANGING ROOMS & DOCTORS' COURT**

Drawing Title: **SCHEME DESIGNS - PLAN, ELEVATIONS & SECTIONS**

Scale: 1:100 BUT NOT TO BE SCALED.  
Drawing No: 007/EABQ/01775/2014



4. First Floor Plan Detail Section 1:100



Ground Floor 1:100